

July 15<sup>th</sup>, 2009  
NUSS09@FNAL

# ***T2K & NOvA***

## ***-ACCELERATOR EXPERIMENTS UNDER CONSTRUCTION-***

T. Nakaya (Kyoto)

1

# OUTLINE

1. Introduction of T2K and NO $\nu$ A
2. Components of the experiments.
  1. T2K beamline/near-detector/far-detector.
  2. NO $\nu$ A beamline/near-detector/far-detector.
3. Status of the T2K and NO $\nu$ A experiments
  1. T2K commissioning and construction schedule/time-line for physics result
  2. FNAL accelerator performance/outlook for NO $\nu$ A and the schedule of the detector construction.
4. Some details of physics sensitivities
  1. Events Reduction
  2. Signal and Background
  3. Physics Sensitivities, and the complementary issues in experiments.
5. Future Prospect
  1. Possible Upgrade (Niki's talk)

# T2K



295 km

# NOvA



NOvA-Far Detector

MINOS Far Detector

810 km



Fermilab

Chicago

Milwaukee

Minnesota

Wisconsin

Iowa

Michigan

Ontario

168 km

© 2007 Europa Technologies  
Image © 2007 TerraMetrics  
Image © 2007 NASA

© 2007 Google™

# 1. INTRODUCTION OF T2K AND NOVA


- The accelerator  $\nu$  oscillation experiments.
  - Probe  $\theta_{13}$  by looking for  $\nu_e$  appearance.
  - Precision measurements of  $\theta_{23}$  and  $\Delta m^2_{23}$ .
  - Search for sterile neutrinos by measuring the neutral current interactions.
  - Look for the difference of  $\nu$  oscillations between  $\nu$  and  $\bar{\nu}$ .
    - CP violation ( $\delta$  in the MNS matrix or new interactions)
    - Matter effect and neutrino mass ordering (sign of  $\Delta m^2_{23}$ ).

	T2K (2004~2009)	NOvA (2009~2013)
<b>Accelerator</b>	J-PARC MR 750kW (design) 	FNAL MI 700kW (330kw current)
<b>Neutrino Beam</b>	2.5 degree off-axis $E_{\text{peak}} \sim 700\text{MeV}$ 	$\sim 14\text{mrad}$ (0.8 degree) off-axis $E_{\text{peak}} \sim 2\text{GeV}$
<b>Near Detector</b>	Fine-Segmented multi-type detectors w/ magnetic field (w/ water target) 	Liquid Scintillator segmented detector (similar as the far detector) 
<b>Far Detector</b>	Water Cherenkov 50ktons (22.5 kt fiducial) 295km away	Liquid Scintillator detector 15 kton 810km away 
<b>Near/Far extrapolation</b>	Hadron production will be measured by CERN NA61 	Hadron production will be measured by FNAL MIPP 


# T2K SENSITIVITY

$\theta_{13}$  from  $\nu_e$  appearance

$\theta_{23}$  from  $\nu_\mu$  disappearance



Assuming  $\theta_{23} = \pi/4$  and  $\delta = 0$




T2K (Stat. only)  
@ full Intensity

$\sin^2 2\theta_{23}$

# NOvA SENSITIVITY


$\theta_{13}$  from  $\nu_e$  appearance

90% CL Sensitivity to  $\sin^2(2\theta_{13}) \neq 0$



$\theta_{23}$  from  $\nu_\mu$  disappearance

Sensitivity Contours (15 kt\*36E20 POT)



It is a parameterized calculation,  
which needs to be redone with  
a full reconstruction.

# IMPORTANT THINGS FOR EXPERIMENTS

- The experiments must be realized.
- It is a fun time for an experimentalist to work for
  - the design stage of the experiment
  - the construction of the new equipments
  - the beginning of the commissioning of the experiment
  - the stage that the important physics results are produced.
- You can consider new ideas and possible upgrade of experiments any time.
  - It is the reason why you are physicist, I guess.
  - Examples
    - Physics sensitivity of T2K with anti-neutrino beams
    - Neutrino Interaction physics in the T2K and NOvA near detectors.
    - :
  - Summer school/Workshop is a good opportunity for us to discuss/exchange these ideas


## 2. COMPONENTS OF THE EXPERIMENTS.

- Accelerator/Neutrino Beams
- Near Detectors
- Far Detectors

Intense beam

High Resolution  
Near detector


Gigantic  
Far detector



## 2. COMPONENTS OF THE EXPERIMENTS.


*T2K*

# J-PARC ACCELERATORS [750kW DESIGN]




# OFF-AXIS $\bar{\nu}$ BEAM


**Tuned at oscillation maximum**



## Decay Kinematics



## ◆ Quasi Monochromatic Beam



## Statistics at SK w/o osci.

(OAB 2.5 deg, 1 yr, 22.5 kt,  
40 GeV protons)

~ 2200  $\nu_\mu$  tot


~ 1600  $\nu_\mu$  CC

$\nu_e$  ~0.4% at  $\nu_\mu$  peak

# PRIMARY BEAM-LINE



**Preparation Section**



Assumed Beam Loss

750W@Prep.  
250W@FF.  
(1W/m @ ARC)

**ARC Section**




**Final Focusing Section**




- Beam-line tunnel was completed in December 2006
- Installation finished in 2009

# TARGET STATION AND HORNS


320kA current for the horn system




Beam Window  
With pillow seal




Support Module



Huge  
He vessels






# T2K NEAR DETECTORS



# ND280 OFF-AXIS



## Neutrino Beam Monitor



A CC1 $\pi$  interaction in the P0D, with full-bunch background

- Volume:
  - $3.5 \times 3.5 \times 7.0 \text{m}^3$
- P0D:  $\pi^0$  Detector
- FGD+TPC: Charged Particle tracking
- EM calorimeter
- Side-Muon-Range Detector

# FAR DETECTOR: SUPER-KAMIOKANDE IV




Super-K III

## 2. COMPONENTS OF THE EXPERIMENTS.

*NO $\nu$ A*


# FERMILAB NUMI BEAM

- 120 GeV
- $5E13$  PPP
- 320 kW  $\rightarrow$  700 kW




# OFF-AXIS BEAM FEATURES

- Narrow energy distribution
- Tuned Energy by selecting off-axis angle
  - Maximize  $\nu_e$  appearance
  - Minimize  $\nu_\mu$
- Higher Intensity at a given energy
- Suppressed high energy tail
  - Reduces NC contamination





# INTEGRATION PROTOTYPE NEAR DETECTOR (IPND)

- Constructing prototype detector to run on the surface near MINOS Surface Building
- 4 Blocks (6+)
- 2.9m wide
- 4.2m tall
- 8.4m long (15.3m)



# SITE FOR FAR DETECTOR: ASH RIVER, MN



- This site is at 810 km from Fermilab, 11.77 km off-axis
- Farthest available site in the U.S. along the NuMI beam

# FAR SITE STATUS




**Groundbreaking: Friday, May 1, 2009, at 2:30 p.m.**



# NONA FAR DETECTOR

- 15 ktons
- 15.6m x 15.6m x 68m
- 1003 liquid scintillator planes, (~73% active)
- Scintillator cells  
3.8 x 6.0 x 1540 cms
- Read out from one side per plane with APDs
- Expected average signal at far end of 30pe




### 3. STATUS OF T2K AND NOVA.

## *T2K*

- T2K Commissioning/Construction status


# THE NEUTRINO BEAM-LINE



# FIRST SHOT OF THE PROTON BEAM



## SSEM

(Segmented Secondary Emission Monitor)



# HORN FOCUSING: MUON MONITOR SIGNAL

Horn off





**SI Fit peak**  
**73.2 pC**

**X CENTER**    **Y CENTER**  
**-4.84 cm**    **-2.54 cm**

**X SIGMA**    **Y SIGMA**  
**135.5 cm**    **147.1 cm**

Horn on



**SI Fit peak**  
**159.3 pC**

**X CENTER**    **Y CENTER**  
**+3.60 cm**    **+8.35 cm**

**X SIGMA**    **Y SIGMA**  
**118.1 cm**    **113.7 cm**




MUMON Silicon PIN photodiode array

# ACHIEVEMENT IN APRIL AND MAY

- Nominal intensity:  $\sim 4 \times 10^{11}$  p/bunch, 1 bunch/spill ( $\sim 0.1\%$  of design intensity)
- Superconducting combined-function magnets are working well as expected.
- Beam monitors are working well.
  - Intensity monitors, beam position monitors, beam profile monitors are working well.
  - Beam position at the target is confirmed with the fluorescent plate.
  - Muons from  $\pi$  decays are observed by MUON MONITOR behind the beam dump.
- The effect of the electromagnetic horn is confirmed.
- Successfully passed the government inspection.




# ON-AXIS DETECTOR: INGRID



- Assembly of 228 tracking planes completed
- **Looked for neutrino events with one module.**
- Half modules have been installed. (The rest of modules will be installed in August)

# OFF-AXIS DETECTORS






- Most detectors have been arrived in J-PARC.
- Installation will begin in September.
- The detector will be ready by the end of 2009.

# HAMAMATSU MPPC

## ○ Multi-Pixel-Photon-Counter

- Multi-pixel APD operating with Geiger mode (667 pixels.) specially developed for T2K
- New type photo-sensor w/ excellent performance.
- Insensitive to magnetic field.

## ○ 60,000 production for T2K



# FROM NOW

- Full horns and ND280 soon
- **100kW trial** in JFY2009
- Physics run from **2010 → fist result**
- Beyond 100kW: 100→750kW(Design)
  - Beam loss control
  - Linac 400 MeV energy recovery and upgrade of the RCS injection system
  - **Important Physics result around 2012 (my personal view)**
- Long-term plan toward power frontier (**~1.7 MW**)
  - KEK roadmap
  - Anti-ν running




### 3. STATUS OF T2K AND NOvA.

*NOvA*

# NUMI PROTONS

FY08 Integrated Beam to NuMI




**The amount of beam is limited by losses in the Main Injector tunnel**

**NuMI beam power:  
290KW nominal mix mode  
330KW NuMI-only mode**

**11 Batch Slip Stacking  
(9 batches for NuMI) was implemented in April 2008**

**A few places where greater slope was due to non stacking periods and NuMI received all 11 btaches**



■ Fiscal Year 09 Integrated Beam to NuMI — Design — Base



NOvA Ground Breaking  
1 May 2009

# PROGRESS

- Advances on all fronts
  - Accelerator and NuMI Upgrades (ANU) extensive shutdown plans beginning upgrades necessary for 700kW operation.
  - Module components prepared, or contracts made for prototype detector. (Integration Prototype Near Detector (IPND), and more, where approved)
  - Assembly prototypes under construction
    - Static leak tests, full height, in C0, full pressure.
    - FSAP, Full Size Assembly Prototype
    - FHEP, Full Height Engineering Prototype , 31 planes 2 modules wide

# MODULE ASSEMBLY AND TESTING



Bubbler Construction



Testing Bubblers



Extrusion production



Rolling Lifting Fixture




Adhesive Dispenser



# FAR DETECTOR

The cells are made from 32-cell extrusions.

12 extrusion modules make up a plane.  
The planes alternate horizontal  
and vertical.



There are 1003 planes, for a total mass of 15 kT. There is enough room in the building for 18 kT, which can be built if we can preserve half of our contingency.

The detector can start taking data as soon as blocks are filled and the electronics connected.

An admirer



# APPROXIMATE SCHEDULE OF NONA

- May 2007: US DOE CD-1 Approved
- Sep 2007: Cooperative Agreement signed
- Nov 2007: US DOE CD-2/3A review
  - Baseline, advanced procurement
- Dec 17, 2007 R&D funding for FY08 cut to zero.
- July 1, 2008 Supplementary funding restarts progress
- Sept 15, 2008, Oct 24, 2008: CD-2, CD-3A Approved
- April 2009: Reinvestment Act, and FY09 funding approved
- May 1, 2009 Groundbreaking at Ash River
- **Fall 2009 Begin Building IPND modules**
- **Winter 2009/10 Begin building IPND Blocks**
- **Summer 2010 Begin operation of IPND (prototype Near Det.)**
- **Summer 2010: Beneficial Occupancy of the Far Detector building**
- **Winter 2011: Begin to Install FD, Data taking after a few kT installed**
- **2013 Installation Complete**

## 4. PHYSICS SENSITIVITY

*T2K*

# T2K MEASUREMENTS



Oscillation Probabilities when  $\Delta m_{12}^2 \ll \Delta m_{23}^2 \approx \Delta m_{13}^2$

➤  $\theta_{23}$ :  $\nu_\mu$  disappearance

$$P_{\nu_\mu \rightarrow \nu_x} \approx 1 - \underbrace{\cos^4 \theta_{13}}_{\sim 1} \cdot \sin^2 2\theta_{23} \cdot \sin^2 \left( 1.27 \Delta m_{23}^2 L / E_\nu \right)$$

➤  $\theta_{13}$ :  $\nu_e$  appearance

$$P_{\nu_\mu \rightarrow \nu_e} \approx \underbrace{\sin^2 \theta_{23}}_{\sim 0.5} \cdot \sin^2 2\theta_{13} \cdot \sin^2 \left( 1.27 \Delta m_{23}^2 L / E_\nu \right)$$


common

➤  $\delta$ : CP violation (T2K-II)

$$A_{CP} = \frac{P(\nu_\mu \rightarrow \nu_e) - P(\bar{\nu}_\mu \rightarrow \bar{\nu}_e)}{P(\nu_\mu \rightarrow \nu_e) + P(\bar{\nu}_\mu \rightarrow \bar{\nu}_e)} \cong \begin{cases} \sim 0.18 & (\sin^2 2\theta_{13} = 0.1) \\ \sim 0.58 & (\sin^2 2\theta_{13} = 0.01) \end{cases} \cdot \sin \delta$$

# Measurement of $\theta_{23}$ , $\Delta m_{23}^2$

Use 1 ring  $\mu$ -like events  
 (= **Quasi-Elastic** enhanced sample)  
 to reconstruct neutrino energy.






5 years

**No oscillation**

$\Delta m^2 = 2.5 \times 10^{-3} \text{ eV}^2$

$\Delta m^2 = 2.0 \times 10^{-3} \text{ eV}^2$



(assuming  $\sin^2 2\theta_{23} = 1.0$ )




Ratio of  $E_\nu$  to non-oscillation

# OSCILLATION PARAMETER FIT

Input:

$$\sin^2 2\theta_{23} = 1.00$$

$$\Delta m^2 = 2.7 \times 10^{-3} \text{ eV}^2$$



# $\theta_{13}$ measurement ( $\nu_e$ appearance search)



$\sin^2 2\theta_{23}=1$  and  $\delta=0$  are assumed.

Signal:

- 1ring e-like event (CC QE sample)

Background:



- beam  $\nu_e$  contamination (0.4% of  $\nu_\mu$ )
- mis-reconstructed  $\pi^0$  event



# BACKGROUND SUPPRESSION


( $\Delta M^2 = 2.5 \times 10^{-3} \text{eV}^2$ ,  $\sin^2 2\theta_{13} = 0.1$ )

1. FCFV,  $E_{\text{vis.}} > 100 \text{MeV}$
2. single ring
3. e-like PID
4. no decay-electron
5.  $0.35 < E_{\nu}^{\text{rec}} < 0.85 \text{GeV}$
6.  $\cos\theta_{\nu e} < 0.90$
7.  $M_{\pi^0} < 100 \text{MeV}/c^2$  ( $\pi^0$  fitter)
8.  $\Delta L < 80$  ( $\pi^0$  fitter)




# $\Theta_{13}$ SENSITIVITY (w/ $\Delta\text{BG}_{\text{SYS}}=10\%$ )

90% C.L. sensitivity





Sensitivity versus time



# T2K PHYSICS SENSITIVITY

$\nu_e$  appearance  
(Strong  $\delta$  dependence)



~10 times improvement from CHOOZ




# CP VIOLATION STUDY


$\bar{\nu}$  beam is an option

(Note: Old study with 2° off-axis)

## Flux



## CC interaction




## 4. PHYSICS SENSITIVITY

*NO*  $\nu A$

# E CC EVENT

Event 40 from /data/pc2\_3/oa/ta\_nuecc\_lowE010.root

XStripVsPlane



$\nu_e p \rightarrow e^- p \pi^+$


$E_\nu = 2.5 \text{ GeV}$

$E_e = 1.9 \text{ GeV}$

$E_p = 1.1 \text{ GeV}$

$E_\pi = 0.2 \text{ GeV}$


YStripVsPlane




# $\mu$ CC EVENT

Event 194 from /data/minos/oa/tavc\_numucc\_lowe001.root

XStripVsPlane



YStripVsPlane



2GeV muon  
CC event

# $\mu$ CC EVENT

$$\nu_{\mu} n \rightarrow \mu^{-} n \pi^{+} \pi^{0}$$

$$E_{\nu} = 2.8 \text{ GeV}$$

$$E_{\mu} = 0.5 \text{ GeV}$$


$$E_n = 1.0 \text{ GeV}$$

$$E_{\pi^{+}} = 0.4 \text{ GeV}$$


$$E_{\pi^{0}} = 1.8 \text{ GeV}$$

Event 3078 from /data/pc2\_3/oa/ta\_numucc\_lowE011.root

XStripVsPlane




YStripVsPlane




# NC EVENT

Event 3440 from /data/pc2\_3/oa/ta\_numunc\_highE020.root

XStripVsPlane





YStripVsPlane



$\nu_\mu N \rightarrow \nu_\mu p \pi^0$   
 $E_\nu = 10.6 \text{ GeV}$   
 $E_p = 1.04 \text{ GeV}$   
 $E_{\pi^0} = 1.97 \text{ GeV}$


# ELECTRON IDENTIFICATION FOR NOVA (TDR ANALYSIS)



~20 variables in Neural Net

Example distributions

Overall efficiency ~30% (optimizable)





ANN Output

# DETECTOR PERFORMANCE

- Optimize Figure of Merit ( $FOM = \text{sig} / \sqrt{bkd}$ ) performance separately for  $\nu$  and anti- $\nu$
- Use  $18E20$  POT,  $\sin^2(2\theta_{13}) = 0.1$ ,  $\Delta m^2 = 2.4E-3$ , no matter effects
- Upgrades to neutrino event generator
- Updates to predicted neutrino flux
- Updated detector mass and configuration
  - 15kT, slightly shorter modules, photodetector readout


# PERFORMANCE OPTIMIZATION

Combined Figure of merit 18.0



# 3 SIGMA SENSITIVITY TO $\sin^2(2\theta_{13}) \neq 0$

**3  $\sigma$  Sensitivity to  $\sin^2(2\theta_{13}) \neq 0$**




Sensitivity vs  $\delta$   
for non-zero  
 $\sin^2(2\theta_{13})$  at 700kW,  
1.2MW, and 2.3MW

# MASS HIERARCHY RESOLUTION

If you assume a measurement of  $P(\nu_e)=0.02$ , what does that imply about  $\theta_{13}$  and the mass hierarchy, and how can you distinguish them.


Determine  $P$  using anti-neutrinos and/or measure  $\theta_{13}$  in reactor experiment.

$\sin^2(2\theta_{13})$  vs.  $P(\bar{\nu}_e)$  for  $P(\nu_e) = 0.02$




# 95% CL SENSITIVITY TO THE MASS ORDERING

95% CL Resolution of the Mass Ordering




95% CL Resolution of the Mass Ordering



# MEASUREMENT OF $\sin^2(2\theta_{23})$

Sensitivity Contours (15 kt\*36E20 POT)




If  $\sin^2(2\theta_{23}) = 1$ ,  
then it can be  
measured to 0.004.

Otherwise, it can  
be measured to  
~0.02.

# CP PHASE

- Assuming a normal hierarchy, and oscillation at the starred point, NOvA measurement resolves the mass hierarchy, and constrains  $\delta_{CP}$  to the top half of the plane.



## 5. FUTURE PROSPECT

- The topics are main subjects of the next lectures.
- Only introduce the Japanese scenario briefly.

# T2K BEYOND

Study Symmetry Violation  
between  $\nu$  and  $\bar{\nu}$


J-PARC Upgrade  
KEK Roadmap  
→ 1.7MW

Best Optimization


Huge  $\nu$  detector  
• Water Cherenkov  
• Lq. Ar TPC  
 $O(\sim 100\text{k})\text{ton}$

*Hyper-K*



water C



GUT  
Proton Decay



# Scenario 1 (Hyper-K @ Kamioka)



295km


CP discovery on  $\delta$  in the range of  $20^\circ \sim 160^\circ$  and  $200^\circ \sim 340^\circ$

# Scenario 2


- 100kton Lq. Ar TPC @ 658km?
- $\nu$  beam only

$\nu_e$  Spectrum 札幌

$\sin^2 2\theta_{13} = 0.03$ , Normal Hierarchy



## CP Measurement Potential



Beam  $\nu_e$   
Background

# CONCLUSION

- **The next generation  $\nu$  oscillation experiments beyond T2K and NO $\nu$ A depend on the outcome of the on-going experiments (MINOS, OPERA, T2K, NO $\nu$ A, DCHOOZ, Daya-Bay, RENO, and many double beta decay experiments)**
- **So, the future depends on YOUR discovery.**

# BACKUP -T2K-

69


# Status of J-PARC

MR commissioning May, Jun, Dec in 2008



3 GeV RCS beam commissioning succeeded in Nov. 2007


Linac succeeded in 181 MeV acceleration in Jan, 2007



## 3.1 ニュートリノビーム/J-PARC




## 3.1 ニュートリノビーム/J-PARC



# 3.1 ニュートリノビーム/J-PARC



# PRIMARY BEAM LINE



- Bend proton beam by  $84.5^\circ$
- Preparation section
  - 11 normal conducting magnets
  - 750W beam loss allowed
- Arc section
  - 28 superconducting combined function magnets (first application)
  - D2.6T, Q18.6T/m, L=3.3m
  - 1W/m loss allowed
- Final focusing (FF) section
  - 10 normal conducting magnets
  - 250W loss allowed

Control of beam loss is critical issue

# Superconducting magnets

- 26 (/28) mags, 11 (/14) "doublets" completed
- 6 doublets already installed in the tunnel
- Up to 28 mags, 12 dblt's in FY2007 (by Mar.2008)
- 4 corrector mags are produced by BNL. 2 are delivered to KEK, 2 more being fabricated
- Magnet safety system (MSS) by Saclay
  - Hardware being constructed almost on time (Delivery to KEK in June)

Superconducting magnets (doublet) in Tunnel




Correctors





MSS



# SUPERCONDUCTING MAGNETS



Two magnets in cryostat “doublet”  
14 doublets + 2 spare doublets  
+ 4 corrector magnets by BNL



Transport to  
tunnel  
Feb.8, 2008



Alignment  
Apr.15, 2008



Monitor Installation  
@ inter-connect

**SCFM** : Superconducting Combined Function Magnet

D: 2.6 T, Q: 18.6 T/m, Length: 3.3m, Current: 7,345A@ 50GeV

- 11 doublets in beam-line, Cryogenics installation on time.
- Entire system will be completed by December 2008

## Normal conducting PRIMARY LINE COMPONENTS magnets

- **11 mags in prep.section installed and aligned.**
- Installation of FF magnets starts in March 2008.

## Misc.

- Installation of vacuum components / beam plug started.
- Level meas. in progress to monitor ground sink.



Position: 20 x ESMs

Profile: 19 x SSEM s

Intensity: 5x CTs

# PROTON BEAM MONI

- **Being assembled**
- **Installation started in prep sect**

Loss: 50 x Ionization chambers

- **Twenty monitors are purchased in this FY**

OTR detector (provided by Canada)

- Provide all-time profile just in front of target
- **Mirrors, rad-hard camera delivered**
- Manufacturing, assembling in progress

Electronics

- FADC for CT/ESM being produced by US
- FADC for SSEM prepared by Korea


ESM




CT



SSEM



OTR




Installed monitor chamber





# TARGET STATION




6




- Overcame water food problem during excavation in early 2007
- Installation of the helium vessel (~470ton, 1000m<sup>3</sup>) finished, passed vacuum test in Nov. 2007 as scheduled
- Construction of surface building starts soon and will finish in June 2008.

# Target Station




- 40t crane for remone maintenance installed on March '08
- Construction of the building to be completed in June 200



# APPARATUS IN THE TS VESSEL





Beam Window  
With pillow seal



## Support Module






Beam window @RAL

Monitor chamber @TRIUMF

Mockup monitor  
Pillow seal flange  
for monitor chamber







Beam window and monitor chamber are under assembly at RAL/TRIUMF and will be installed into TS from July 2008.

# 電磁ホーン(π収束装置)

## 3 ホーンシステム

- 320kA運転で長期試験





# FULL SYSTEM SETUP TEST OF HORN AND DEMONSTRATION OF ITS REMOTE MAINTENANCE SCENARIO AT FUJI, KEK

In preparation now.

The 320 kA test operation soon.


Necessary improvements are identified and being solved.

**Support Module**



**3<sup>rd</sup> Horn**


**Full Setup**



**Hung by remote sling tool**





# MARKER




- Full prototype delivered in Dec. '07
- He gas flow test, achieve 650Nm<sup>3</sup>/h (200m/s)

## CFX analyses (STFC RAL)



CFX




$\Delta T \sim 200K \sim 7MPa$  (Tensile 27MPa)


# 標的

CFX


- グラファイト:
  - 26mm(D)x900mm(L)
- ヘリウム冷却





$\Delta T \sim 200K \sim 7MPa$  (Tensile 27MPa)



Baffle (RAL)  
Target  
1<sup>st</sup> horn




# Beam VOLUME



2008/03/07

# DECAY VOLUME


- Upstream part (20cm<sup>t</sup> Iron) was installed & tested in Nov 2007.
- Anchor frame for BD core was embedded in concrete in Feb. 2008.
- Civil construction of downstream part will be finished by Aug.
- Construction of He vessel:  
for DV: just started, for BD: will start in Aug. 2008.



Downstream part




Anchor frame for BD core




Upstream part

# ビームダンプ

- 98 グラファイトブロック
- Core will be Installed into He vessel in Oct/Nov 2008.



500°C with 3MW  
[Assuming phase-I target]




89  
1<sup>st</sup> assembled module

# ミューオンモニター



- パルス毎にニュートリノビームをモニター
  - 強度、方向、プロファイル
- フェルミ研T968として、NuMIビームラインでプロトタイプの長期試験中
- 2008年冬に設置予定。

Ionization chamber array

Beam



Si PIN diode array



NuMI/MINOSに  
設置されたT2K-  
ミューオンモニター  
試作機

26pZj: 15:45 ~

□ 松岡  
□ 久保



# SUMMARY OF STATUS

	Conceptual Design	Engineering Design	Real Production	Installation
Proton Beam monitor				Feb.~
Superconducting magnets				Feb~
Cryogenics				Apr~
Normal Conducting magnets				
Vacuum system				
Target				Aug.~
Horn				Aug.~
Target Station				
Beam Window				Jul~
Decay Volume				
Beam Dump				Aug~
Muon monitor				08/09

- All components are in production phase
- Installations are starting as scheduled

# 前置ニュートリノ測定器: ND280

## オフ軸測定器






ニュートリノモニター:  
INGRID



# 前置測定器

## On-axis neutrino monitor

- Monitor
  - Profile
  - Direction
  - Intensity (& Energy)
- Iron-Scintillator sandwich detector
  - 1mx1mx10cm Iron
  - 1.25cm thick extruded Scinti.
  - New Photo-Sensor (MPPC/SiPM)



□ Conceptual design optimization versus PIT

## Off-axis detector

- Measurement of  $\nu$  flux and  $\sigma$  in the SK direction.
- Detector components.
  - UA1 magnet (0.2T)
  - TPC
  - Fine-Grained Scintillator detector (FGD)
  - Lead/Scintillator tracking detector for  $\pi^0$
  - Electromagnetic Calorimeter
  - Muon Range Detector in mag
- Key technologies
  - Photo-sensor, Micromegas

# OFF-AXIS DETECTOR

- Measure  $\nu_\mu$  flux: <5%
- Measure  $\nu_\mu$  energy scale: <2%
- Measure intrinsic  $\nu_e$  content of beam: <10%
- Measure non-CCQE backgrounds for both  $\nu_\mu$  disappearance and  $\nu_e$  appearance: <10%
- Magnetic field, fine segmentation, excellent tracking
- Major non-Japanese contributions
- High complexity and non-trivial integration




# 280M DETECTOR HOLE CONSTRUCTION



- 17.5m- $\phi$  x 33.5m deep hole excavation finished in Jan 2009
- Underground floors being constructed.
- UA1 magnet installation Apr-Jun, 2008
- **Construction is on schedule**



# INGRID: ニュートリノビームモニター




## ○ 7+7+2モジュール



- 10,000事象/モジュール/日
- ニュートリノ強度、ビーム方向、スペクトル安定性をモニター

## ○ 120×5×1cm<sup>3</sup>シンチレータ



- 約10,000本
- 波長変換ファイバー読出し
- 光測定器: 浜フォトMPPC
- 平均光量:  $\sim 15$ p.e./cm



## ○ 2009年4月測定開始



# オフアクシス測定器



- 測定器容量:
  - $3.5 \times 3.5 \times 7.0 \text{m}^3$
- P0D  $\pi^0$  測定器
- FGD+TPC:
  - 荷電カレント反応測定
- 電磁カロリメータ
- サイドミュオン飛行測定器





A CC1 $\pi$  interaction in the P0D, with full-bunch background

# P Ø D






- Scintillator bars – lead/brass sandwich – water targets. Mass: 17.6ton total, **2.9ton water**
- Optimized for **NC  $\pi^0$**  production measurements
- Runs with/without water: C/H<sub>2</sub>O scaling
- **17,000 NC  $1\pi^0$  events/year in water**
- **MINERVA bars, WLS fibres, MPPCs, TRIP-t electronics**
- **Construction: May-December 2008**

- 3 Super-PØDules
  - ◆ Upstream ECAL (3200 kg)
    - 7 PØDules
    - 7 4mm-thick lead radiators
  - ◆ Target (11000 kg)
    - 2857.3 kg water
    - 26 PØDules
    - 25 1.6mm brass radiators
    - 25 Water target layers
    - Split into 2 sub-units for pre-installation handling
  - ◆ Central ECAL (3200 kg)
    - 7 PØDules
    - 7 4mm-thick lead radiators
- Total Mass is 17600 kg







# ECAL

- Reconstruct  $\pi^0$ , identify  $e/\mu/\pi$
- Lead-scintillator sampling calorimeter
- 4cm x 1cm scintillator, WLS fibre, MPPCs, TRIP-t readout
- 32 layers, 1.75mm Pb,  $10X_0$
- DS ECAL ready for installation summer 2009; Barrel in 2010



# INTEGRATION

- Complex dependencies and interactions in space and time
- Technical Board, installation coordinators
- Central 3-D pit description, including services routing
- Central project file
- Seismic studies
- Environmental studies (temperature, humidity)



# UA1 MAGNET


- UA1実験のダイポールマグネットをCERNより輸送。
  - J-PARCに設置終了
- TPCと組み合わせて運動量測定
  - 0.2Tで運転
  - 高精度＋大立体角で荷電粒子測定。



# FINE GRAIN DETECTORS


- ニュートリノバーテックス測定器
- 1cm × 1cm シンチレータ, 波長変換ファイバー + MPPC
- 2009年夏にインストール

Simulated CCQE interaction



# TPC


- 3TPC, **MicroMegas** 読み出し (8mm × 8mm パッドサイズ)
- 10% 運動量分解能 ( $p < 1 \text{ GeV}/c$ ),  $\sim 10\%$   $dE/dx$  分解能
- MicroMegas試作機はCERNでテスト。=> 生産開始へ!
- 2009年夏に2台のTPCを設置予定。



MM1\_001 (stiffener V2) (HARp tests 09/19/2007)



- a 30  $\mu\text{m}$  thick 440 Lpi woven micromesh is embedded between 2 layers of pyralux
- 4 layers PCB with internal shielding layer & 6,9x9,7 mm pads with 7x9,8 mm pitch
- 128  $\mu\text{m}$  amp. gap / 12 x  $\phi 0,5$  mm pillars per pad / « stretched » mesh procedure
- 93% of PCB surface is active area / less than 2 faulty pads per module

adeibat@cea.fr - WP4 "bulk" Micromegas & WP5 Module Mechanicals Status, KEK ND280/T2K/TPC meeting 09/26/2007




# SIDE MUON RANGE DETECTOR

- 磁石ヨークのギャップ(1.7cm厚)にシンチレータ挿入。
  - 7mm厚シンチレータ – 波長変換ファイバー + MPPC
- ミューオン検出、外部からの事象のVETO、宇宙線トリガー




# READOUT ELECTRONICS

- Two solutions for Front End Electronics:
  - UK system using FNAL **TRIP-t chip**: INGRID, P0D, ECAL, SMRD
  - French system using Saclay **AFTER chip**: FGD, TPC
- Prototypes for both systems operational
- **Back End Boards** and DAQ system by RAL (common to all)
- Slow Control: MIDAS (TRIUMF)



MPPC spectrum with prototype TFB, BEB, and DAQ

AFTER chip and card





TFB system in US lab


# SUPERKAMIOKANDE

- Refitted SuperK, major next upgrade: **electronics** (higher dynamic range – faster – no dead time – stability >10 years)
- Installation starting September 2008
- New Online, spill time information transferred from J-PARC over private line, allow to flag and record  $\pm 500\mu\text{s}$  around each spill
- Reconstruction and simulation will be adapted

## New electronics and DAQ system for the SK detector






## Preparation of the new system is on schedule!



# CERN-SPS NA61 (SHINE) EXPERIMENT



- Measure  $\pi/K$  prod. from Graphite target to predict
  - Near and far energy spectra ( $<2\sim3\%$ )
  - Near to far spectrum extrapolation ( $<2\sim3\%$ )
  - $\nu_e$  contami. (from K,  $\mu$ ) ( $<2\sim3\%$ )
- **First data taking in Oct., 2007 (1month)**
  - Beam: 30GeV proton
  - Thin target ( $2\text{cm}^t$  4%int):  $\sim 500\text{k}$  int.
  - Replica target (90cm, 80%int):  $\sim 180\text{k}$  int.
- Measurements in 2008 planned



First look of data  
(PID, acceptance not corrected)

# T2K-I sensitivity with systematic errors

- normalization ( 5%)
- non-qe/qe ratio ( 5%)
- E scale ( 2%)
- Spectrum shape (20%)
- Spectrum width ( 5%)



# FUTURE PROSPECTS IN A FEW-YEAR SCALE

- We are requesting 100kW operation of MR for more than 10<sup>7</sup>s (several months) to the accelerator group before 2010 summer shutdown
  - This is vitally important, in order to get the 1<sup>st</sup> result with enough impact.


To achieve the request, to increase rep. rate is a preferable solution, without significant hardware upgrades:

Cycle: 3.04 → 2.04sec, 30GeV

{ Acc 1.9 → 1.1sec  
 { Reset 0.87 → 0.67sec


- ◆ # of bunches to be recovered from 6 to 8 (design).
- ◆ Nominal beam power: 30GeV-9uA (270kW), to be achieved in JFY2012 or earlier.

[J-PARC Director's order: "Nagamiya Chart"]




# FUTURE PROJECTS

- Future projects to investigate Lepton sector CPV / neutrino mass hierarchy
  - Key components: J-PARC power upgrade (750kW → \*\*MW) & massive far detector(s)
  - Proton decay
  - Intensive discussion is being started to prepare the best proposal towards 2012.
- Need continuing upgrades for accelerator components for the purpose.
  - For Linac: 181MeV → 400MeV with ACS Installation
    - Just after completion of J-PARC: Apr.'09 ~
    - 4 year (3 year in case R&D in 2008 goes smoothly)
  - For RCS/MR RF: Improvement for the magnetic alloy cut core
    - To achieve the high field acceleration as designed (25kV/m)
    - To improve production process / Water → Oil (paraffin) cooling
    - This will further increase the rep. rate
  - For MR Fx kicker:
    - To improve slow rise time 1.6us → 1.1us (#b 6 → 8)
    - Without causing discharge
  - 30GeV → 40(50)GeV energy boot-up
- MR intensity upgrade scenario
  - Increasing repetition rate (cycle=3.04 to 1.92sec)
  - Reduce harmonic number of RCS from 2 to 1
    - 1x8 injections instead of 2x4: Almost twice of beam injected to MR.
  - KEK roadmap: 1.66MW
- We will learn a lot more by the successful operation of the neutrino beam-line !



# Hyper-Kamiokande



~0.5Megaton fid vol. (0.27Mton x 2 detectors)  
Needs ~100,000PMTs (assume 20% coverage)

# BACKUP -NOVA-




112

# PROTON PLANS


	<b>Present Operating Conditions (May 2007)</b>	<b>Proton Plan Multi-batch Slip-stacking in MI</b>	<b>NOvA Multi-batch Slip-stacking in Recycler</b>
<b>8 GeV Intensity (p/Batch)</b>	4.3 - 4.5x10 <sup>12</sup>	4.3x10 <sup>12</sup>	4.3x10 <sup>12</sup>
<b>Number of 8 GeV Batches to NuMI</b>	7	11	12
<b>MI Cycle Time (sec)</b>	2.4	2.2	1.3
<b>MI Intensity (protons per pulse or ppp)</b>	3.3x10 <sup>13</sup>	4.5x10 <sup>13</sup>	4.9x10 <sup>13</sup>
<b>MI to NuMI (ppp)</b>	2.45x10 <sup>13</sup>	3.7x10 <sup>13</sup>	4.9x10 <sup>13</sup>
<b>NuMI Beam Power (kW)</b>	192	320	700
<b>Protons/year to NuMI</b>	2x10 <sup>20</sup>	3x10 <sup>20</sup>	6x10 <sup>20</sup>
<b>MI Protons/hour</b>	4.95x10 <sup>16</sup>	7.3x10 <sup>16</sup>	1.3x10 <sup>17</sup>

# THE BASIC DETECTOR ELEMENT

To 1 APD pixel



- Liquid Scintillator
  - 4.1% pseudocumene as scintillant
  - Mineral oil and waveshifters (PPO, bis-MSB)
- PVC cell for primary containment
  - Horizontals: 3.87 cm x 6.0 cm x 15.4 m long
  - Verticals: 3.76 cm x 5.7 cm x 15.4 m long
  - Highly reflective, 15% titanium dioxide
- Looped wavelength shifting fiber to collect light
  - 0.7 mm diameter, double clad, K27 waveshifter
  - Almost perfect mirror, 3.6\*light in 1 fiber
- Avalanche Photodiode
  - 85% quantum efficiency
  - Gain of 100, operate at  $-15^{\circ}\text{C}$
- Low noise amplifier



# APD PHOTODETECTOR

- Hamamatsu  
Si Avalanche Photodiode  
(APD)
  - S11211(X) Custom Variant  
of commercial S8550 SiAPD
  - Custom design to match to  
fiber aspect ratio
  - Bare die mounted to PCB  
via bump bonding



